



F.No.32-13 /AE-IV/JE (6)/OM/2026-27

OULGARET MUNICIPALITY

PUDUCHERRY – 5

Jawahar Nagar, the 09.09.2026

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors by the undersigned for the following work:

Name of Work: Reconstruction of damaged Causeways and 'U' drain at Lenin Nagar, Samipillaithottam in Kamaraj Nagar Constituency.

Sl. No.	Description	Quantity	Rate per unit	Total amount
1.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:1.5:3 (1 cement : 1.5 fine aggregate : 3 graded stone aggregate 20mm nominal size)	4.00 Cum		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:2:4 (1 cement : 2 fine aggregate : 4 graded stone aggregate 20mm nominal size)	4.00 Cum		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 fine aggregate : 10 graded stone aggregate 40mm nominal size)	3.00 Cum		
4.	Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns.	15.00 Sqm		
5.	Steel work welded in built up sections / framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required - in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	240.00 Kgs.		
6.	Cement concrete flooring 1:2:4 (1 cement : 2 fine aggregate : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete - 40mm thick with 20mm nominal size stone aggregate	22.50 Sqm		
7.	6mm cement plaster of mix - 1:3 (1 cement : 3 fine aggregate)	22.50 Sqm		
8.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge - nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	6.00 Cum		
9.	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge - in cement mortar.	5.50 Cum		

10.	Construction of granular sub-base by providing close graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layer with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 of MoRTH specification, 4th Revision - by plant mix method - for grading I material.	6.00 Cum		
-----	---	-------------	--	--

Term and Conditions

1. The quotation will be received by the undersigned up to 3.30 pm on ~~17-09-26~~ and opened at 4.00 p.m. on the same day.
2. The Quotation should be valid for 90 days from the date of opening.
3. The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof and the Oulgaret Municipal Council is competent to accept any quotations.
4. The rate quoted should be inclusive of all charges viz. tax, transporting etc.

Digitally signed by
Arun Ayavou
Date: 08-09-2026
18:48:36
(R.ARUN AYAVOU)
COMMISSIONER

Copy to:

1. Notice Board, Oulgaret Municipality.
2. Oulgaret Municipality Website.