



**OULGARET MUNICIPALITY
PUDUCHERRY – 5**

F.No. 32-09/JE(8)/AE-I/OM/2020-21

Jawahar Nagar, the 31/08/2020

QUOTATION NOTICE

Sub: O.M. - Maintaining reliable power supply distribution system in the Oulgaret Municipality office (Southern side Annexure) building at Jawahar Nagar in Oulgaret Municipality - Quotation Notice - Regarding.

On behalf of the Oulgaret Municipal Council, sealed quotations are invited from eligible contractors firms by the undersigned for the following items as given below:

Sl. No.	Item Code No.	Description of Items	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Ele PSR 2008- 09 1.1.1.2	Supplying and fixing of following size of PVC conduit along with the accessories in surface / recess Conduit including cutting the wall and making good the same in case of recessed conduit as required. Make Avonplast / Vijaya :- 25mm dia	150.00	mtr		
2	Ele PSR 2008- 09 1.1.1.3	Supplying and fixing of following size of PVC conduit along with the accessories in surface / recess Conduit including cutting the wall and making good the same in case of recessed conduit as required. Make Avonplast / Vijaya :- 32mm dia	60.00	mtr		
3	Ele PSR 2008- 09 1230	Providing and fixing 25mm PVC bends. Make : Avonplast / Vijaya - including fixing charges	60.00	1 no.		
4	Ele PSR 2008- 09 1231	Providing and fixing 32mm PVC bends. Make : Avonplast / Vijaya - including fixing charges	20.00	1 no.		
5	Ele PSR 2008- 09 1.5.1	Supplying and drawing of 1.5 sqmm FR PVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC steel conduit / FVC casing and capping as required. Make : Finolex / Polycab:-	540.00	mtr		
6	Ele PSR 2008- 09 1.5.2	Supplying and drawing of 2.5 sqmm FR PVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC steel conduit / FVC casing and capping as required. Make : Finolex / Polycab:-	270.00	mtr		
7	Ele PSR 2008- 09 1.5.3	Supplying and drawing of 4.0 sqmm FR PVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC steel conduit / FVC casing and capping as required. Make : Finolex / Polycab:-	360.00	mtr		
8	Ele PSR 2008- 09 1.5.5	Supplying and drawing of 10.0 sqmm FR OVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC steel conduit / FVC casing and capping as required. Make : Finolex / Polycab:-	360.00	mtr		

9	Ele PSR 2008- 09 1.5.4	Supplying and drawing of 6.0 sqmm FR PVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC steel conduit / FVC casing and capping as required. Make : Finolex / Polycab:-	90.00	mtr		
10	Ele PSR 2008- 09 2.1.10	Supplying, Installing, testing and commissioning of surface / recess mounting, vertical type, 415volts, TPN MCB distribution board and powdered painted, inclusive of 200amps tinned copper busbar, common neutral link, earth bar, din bar for mounting MCB's detachable gland / knock out plate, of following ways (But without MCB's and incommer) as required Make: Siemens / ABB / L & T Hager , 8way (8+24) - TPN, double door, MCB DB, Vertical type.	3.00	1 no.		
11	Ele PSR 2008- 09 1719	Providing and fixing 100 amps. Rating 2pole RCCB 10mA / 300mA. Make Siemnts / ABB / L & T Hagger	3.00	1 no.		
12	Ele PSR 2008- 09 2.2.2.1	Supplying and fixing of 6amps to 32amps rating, single pole 240 volts, 'c' series, miniature circuit breaker suitable for lighting and other loads of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make: ABB / L & T Hager	100.00	no.		
13	PSR 2018- 19 (R) 31.275.1 B	Laying of underground cable direct in ground including metal road cutting, excavation of earth, sand cushion, brick protection, back filling etc., complete. - above 50 sqmm	40.00	mtr		
14	PSR 2018- 19 (R) 31.259.1 D	Supplying of 3.5x95 sqmm underground cable (Paragon / suncab / Empire) complete.- suitable for (60HP to 75HP pump set)/(above 40KVA to 75KVA Genset).	45.00	mtr		
15	PSR 2018- 19 (R) 31.263.1	Making earth pit of G.I. pipe for earthing in earth pit with 40mm dia. G.I. pipe medium class of length 3.05m perforated with 46 Nos of 12mm dia. holes, pipe lowered in bore holes of 150mm dia. and filled in with charcoal and salt in alternative layer of 300mm, the top of G.I. pipe shall be clamped. Earth pit shall be provided with 60cm dia precast ring with 60cm depth alround, covered with R.C.C. precast slab etc. as per I.E. standards.	4.00	no.		
16	PSR 2018- 19 (R) 31.264.1 A	Supplying and fixing of copper wire 8 SWG (4 mm dia) for earthing arrangements including bolt and nuts etc., complete.	20.00	mtr		
17	Ele PSR 2008- 09 1.1.3.2.4	Supplying and fixing of following size of PVC junction box in required position along the line of PVC conduit as required. Make Avonplast / Vijaya:- 32mm dia Junction box four way	30.00	no.		
18	Ele PSR 2008- 09 3175	125 / 200 / 250 / 315 A DIN HRC fuse base Make: Standard / Havells / C & S	12.00	no.		

19	NPSR	Providing and fixing of HRC fuse clamp set (RCC pole)	1.00	Job		
20	NPSR	Providing and fixing of RCC pole clamp set	2.00	no.		
21	PSR 2018- 19 (R) 6.1.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in - cement mortar 1:4 (1 cement : 4 coarse sand)	1.00	cum		
22	PSR 2018- 19 (R) 6.1.1	12mm cement plaster of mix -1:4 (1 cement : 4 fine sand)	30.00	Sqm		
23	PSR 2018- 19 (R) 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.00	cum		
24	PSR 2018- 19 (R) 31.260.1 B	Laying of UG cable and providing termination of cable joint with suitable cable gland, cable socket etc., complete - 3.5/4 x 50 / 3.5/4 x 70 sqmm cable.	6.00	joint		
25	NPSR	Supply of 20W LED tube light fitting (Make: Benio / Bajaj / Philips)	50.00	no.		
26	PSR 2018- 19 (R) 31.252.1 C	Supplying and fixing of 200 Amps capacity cubical wall mounting panel board of size 1400mm x 900mm x 250mm made of 16 gauge CR M.S. sheet painted with two coats of enamel paint, over zinc chromate primer, suitable arrangements for fixing switch disconnector, fuse switches, Voltmeter, Voltmeter Selector switch, Ammeter, Ammeter Selector switch, 3 Nos. of Indicator, 3 Nos. of Toggle switch, 3 Nos. of side lock fuses, 3 Nos. of C.T. Coil etc. The panel board shall include power mat, copper busbar, 3mm thick hylan sheet including internal wiring with provision for interlocking arrangements, copper flat for earthing arrangement linked with shutters and doors. The board shall be mounted on an angle frame of 30mm x 30mm x 6mm with legs. Supplying and fixing of 2 Nos. of TPN CCG / L&T / Siemens / Standard make) 200 Amps, 415 V disconnector switch/cubical switch / fuse switch with fuse links complete. (1 No. for E.D. supply and 1 No. for Diesel Generator supply). Supplying and fixing of 2 Nos of 125 Amps, 415 V disconnector fuse switch/TPN Cubical switch (CG/L&T/Siemens/standard make) with fuse links capacitor motor control (1 number of power capacitor and 1 number of motor control), complete.	2.00	no.		

Terms and Conditions:

1. Quotations should be sealed and subscribed as “**Maintaining reliable power supply distribution system in the Oulgaret Municipality office (Southern side Annexure) building at Jawahar Nagar in Oulgaret Municipality**”.
2. Quotation will be received by the undersigned upto 3.30p.m. on 16-9-2020 and opened at 4.00 p.m. on the same day.
3. The Oulgaret Municipal Council reserves the right to reject any or all the quotations without assigning any reason thereof. The Oulgaret Municipality Council is competent to accept any quotations.

4. The contractor should be able to take up the work and complete the same within a period of 2 months from the date of confirmation of work order issued by this Municipality.
5. The rate quoted should be inclusive of all charges viz, GST, Taxes, Transporting, etc., complete. Payment will be made on completion of work in good and satisfactorily condition by the Engineer-in-charge.
6. The rates quoted should be valid for 90 days from the date of opening of quotation.
7. The Earnest Money Deposit (EMD) should be remitted in the form of Demand Draft in favour of the Commissioner, Oulgaret Municipality at 2% of quoted amount should be enclosed along with the quotation.
8. The EMD will be refunded only after completion of work satisfactorily.


(M.KANDASAMY)
COMMISSIONER

To
Notice Board.