

**OULGARET MUNICIPALITY
PUDUCHERRY – 5**

F. No. 24 -49/JE(3)/OM/2020-21

Jawahar Nagar, the 01-12-2020

QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractor by the undersigned for the following work:

Name of the Work: Provision of Public Taps to the Adi Dravidar Colony at Pillaichavady.

Sl. No.	Description of Items	Quantity	Rate (Rs.)	Unit	Amount (Rs.)
1.	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan),including dressing of sides and ramming of bottoms, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil.	4.00 cum		cum	
2.	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m - all kinds of soil -pipes, cables etc , not exceeding 80mm dia.	280.00 metre		metre	
3.	Supplying and filling in plinth with river sand under floors, including watering, ramming consolidating and dressing complete.	0.75 cum		cum	
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work up to plinth level - 1:2:4 (1 cement : 2coarse sand : 4 graded stone aggregate 20mm nominal size).	2.75 cum		cum	

5.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work up to plinth level - 1: 5: 10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.75 cum		cum	
6.	6 mm cement plaster 1:3 (1 cement : 3 fine sand) finished with a floating coat of neat cement and thick coat of lime wash on top of walls when dry for bearing of R.C.C. slabs and beams.	25.00 sqm		sqm	
7.	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete - internal work - exposed on wall - 20mm nominal outer dia pipes.	18.00 metre		metre	
8.	Providing and fixing brass bib cock of approved quality - 15 mm nominal bore.	6.00 nos.		no.	
9.	Providing, laying and jointing UPVC pipes (Finolex / Jain / Supreme / True bore / Nandi (0.6 Mpa) conforming to IS specification 4985 and ISI marked including transportation to the site lowering to the trenches, laying to proper grade and alignment, testing of joints with required testing equipment, including cost of solvent cement, UPVC specials such as bends, tees, threaded pieces, couplers, reducer, end caps etc., complete all as per IS and CPWD specification. - 50mm dia.	105.00 metre		metre	
10.	Providing, laying and jointing UPVC pipes (Finolex / Jain / Supreme / True bore / Nandi (0.6 Mpa) conforming to IS specification 4985 and ISI marked including transportation to the site, lowering to the trenches, laying to proper grade and alignment, testing of joints with required testing equipment, including cost of solvent cement, UPVC specials such as bends, tees, threaded pieces, couplers, reducer, end caps etc., complete all as per IS and CPWD specification. - 63mm dia.	120.00 metre		metre	

11.	Providing, laying and jointing UPVC pipes (Finolex / Jain / Supreme / True bore / Nandi) (0.6 Mpa) conforming to IS specification 4985 and ISI marked including transportation to the site, lowering to the trenches, laying to proper grade and alignment, testing of joints with required testing equipment, including cost of solvent cement, UPVC specials such as bends, tees, threaded pieces, couplers, reducer, end caps etc., complete all as per IS and CPWD specification. - 75mm dia.	12.00 metre		metre	
-----	---	----------------	--	-------	--

Quotation will be received by the undersigned up to 3.30 pm on 15-12-2020 and opened at 4.00 p.m. on the same day.

EMD amount at 2.00% of the quoted rate should be remitted in the form of Demand Draft in favour of the Commissioner, Oulgaret Municipality. ^{The} Quotation should be valid for 90 days from the date of opening.

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof.

The firm /contractor should complete the work within 15 days from the date of receipt of work order.

The rate quoted should inclusive of all charges viz. Tax, Transporting etc.


(M. KANDASAMY)
COMMISSIONER

Copy to:

Notice board, Oulgaret Municipality.