

F. No. 32-42/ JE(3)/OM/2020-21
OULGARET MUNICIPALITY
PUDUCHERRY - 5

Jawahar Nagar, the 03-03-2022

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors for the work of **"Repair works to the Community Toilet Blocks in Kalapet Constituency"** by the undersigned as mentioned below:

Sl. No.	Description of Item	Quantity	Rate (Rs.)	Unit	Amount (Rs.)
1	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m - all kinds of soil	2.00 cum		1 cum.	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	0.25 cum		1 cum.	
3	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but excluding cost of reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	0.10 cum		1 cum.	
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level - Thermo -Mechanically treated bars (TISCO / VIZAG / IISCO / SAIL / JSW) Fe - 415 or more	8.00 Kg.		1 Kg.	
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 3.5 in foundation and plinth in - cement mortar 1:6 (1 cement : 6 coarse sand)	0.30 cum		1 cum.	

6	Providing and fixing factory made uPVC door frame made of uPVC extruded sections having an overall dimension as below (tolerance ± 1 mm), with wall thickness 2.0 mm (± 0.2 mm) , corners of the door frame to be jointed with galvanized brackets and stainless steel screws , joints mitred and plastic welded. The hinge side vertical of the frames reinforced by galvanized M.S. tube of size 19 x 19 mm and 1mm (± 0.1 mm) wall thickness and 3 nos. stainless steel hinges fixed to the frame complete as per manufacturer's specification - Extruded section profile size 48 x 40 mm	14.00 metres		1 metre
7	Providing and fixing to existing door frames - 24 mm thick factory made PVC door shutters made of styles and rails of a uPVC hollow section of size 59 x 24 mm and wall thickness 2 mm (± 0.2 mm) with inbuilt edging on both sides . The styles and rails mitred and joint at the corners by means of M.S. galvanised / plastic brackets of size 75 x 220 mm having wall thickness 1.0 mm and stainless steel screws . The styles of the shutter reinforced by inserting galvanised M.S.tube of size 20x20 mm and 1mm (± 0.1 mm) wall thickness . The lock rail made up of 'H' section , a uPVC hollow section of size 100 x 24 mm and 2 mm (± 0.2 mm) wall thickness , fixed to the shutter styles by means of plastic / galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multichambered single panel of size not less than 620 mm, having overall thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness . They panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S.rod and fastened with nuts and washers , complete as manufacturer's specification (For W.C. and bathroom door shutter)	4.50 sqm		1 sqm.
8	Providing and laying ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of commercial quality conforming to IS : 15622, of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in colours such as white, Ivory, Grey, Fume red brown ,laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including pointing the joints with white cement and matching pigment etc., complete	6.00 sqm		1 sqm.

9	12 mm cement plaster finished with a floating coat of neat cement of mix - 1:4 (1 cement :4 fine sand)	2.00 sqm		1 sqm.	
10	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design / shape laid in required colour and pattern over and including 50mm thick compacted bed of course sand , filling the joints with coarse sand etc. all complete	13.00 sqm		1 sqm.	
11	Supplying fixing and commissioning of Suguna / Texmo / Sharp 1 HP monoblock pumpset slow speed single phase motor. The rate include the cost of pumpset , pumpset fixing in position and test run etc. complete	1.00 no		1 no.	
12	Providing and fixing wash basin with C.I. brackets, 15mm C.P. brass pillar taps ,32 mm C.P.brass waste of standard pattern , including painting of fittings and brackets ,cutting and making good the walls wherever required - white vitreous china flat back wash basin size 450x300 mm with single 15mm C.P. brass pillar tap	1.00 no		1 no.	
13	Providing and fixing white vitreous china water closet squatting pan (Indian type) - Orissa pattern W.C.pan of size 580x440mm	2.00 nos		1 no.	
14	Extra for using coloured W.C.pan instead of white W.C.pan - Orissa pattern W.C.pan 580x440mm	2.00 nos		1 no.	
15	Providing and fixing ASTM pipes including all ASTM plain& brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing . This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 20mm nominal outer dia pipes	60.00 metres		1 metre	
16	Providing and fixing ASTM pipes including all ASTM plain& brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing . This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 25mm nominal outer dia pipes	30.00 metres		1 metre	
17	Providing and fixing gun metal gate valve with C.I.wheel of approved quality (Screwed end) - 25mm nominal bore	2.00 nos		1 no.	

18	Providing and fixing gun metal gate valve with C.I.wheel of approved quality (screwed end) - 20 mm nominal bore	3.00 nos		1 no.	
19	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI: 12701 marked , with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank - Circular Tank	1000.00 litres		1 litre	
20	Providing and fixing PTMT bib cock of approved quality and colour - 15mm nominal bore, 86 mm long , weighing not less than 88gms	34.00 nos		1 no.	
21	Providing 15 mm dia - GI pipe Nipple 15cm long	20.00 nos		1 no.	
22	Supplying and drawing following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface / recessed steel / PVC conduit as required -2 x 6 sq.mm	40.00 metres		1 metre	
23	Providing Stay wire (7/4.00 mm dia)	5.00 Kg.		1 Kg.	
24	Providing Stay clamp	12.00 sets		1set.	
25	Supplying Bulk head fitting aluminium alloy body heat resistant prismatic glass cover with specially designed gasket (GLS 100W type) Make: Philips/Bajaj	26.00 nos		1 no.	
26	Supplying 1x 40W box type single tube light and fittings with copper choke & starter . Make: Philips/Bajaj	29.00 nos		1 no.	
27	Supplying 9W / 11 W CFL lamp for pendent holder . Make: Philips	25.00 nos		1 no.	

2. Quotation will be received by the undersigned up to 3.30 pm on 11-3-22 and opened at 4.00 p.m. on the same day.

3. EMD amount at 2% of the quoted amount should be remitted in the form of Demand Draft in favour of the Commissioner, Oulgaret Municipality. The Quotation should be valid for 90 days from the date of opening.

4. The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof.

5. The firm /contractor should be able to start the above work immediately on receipt of the work order and complete the same within 30 days from the date of receipt of work order.

6. The rate quoted should inclusive of all charges viz. GST, Transporting etc.

7. Payment will be made on satisfactory completion of the work in all respects within the stipulated period.



**COMMISSIONER
OULGARET MUNICIPALITY**

Copy to:

1. Notice Board, Oulgaret Municipality.