



F. No.32-49/JE(3)/OM/2020-21
OULGARET MUNICIPALITY
PUDUCHERRY – 5

Jawahar Nagar, the 18-04-2022

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors for the work of "Linking of Community Toilet Blocks at Navarkulam burial ground and near Ponniamman temple at Karuvadikuppam to the Under Ground drainage system" by the undersigned as mentioned below:

Sl. No.	Description of Items	Quantity	Rate (Rs.)	Unit	Amount (Rs.)
1.	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil.	25.00 Cum		1 Cum	
2.	Supplying and filling in plinth with river sand under floors, including watering, ramming consolidating and dressing complete.	1.00 Cum		1 Cum	
3.	Supplying and filling with gravel (excluding rock) in trenches, plinth, sides of foundations etc . in layers not exceeding 20 cm in depth consolidating each deposited layers by ramming and watering etc .complete including all lead and lift.	18.00 Cum		1 Cum	
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- all work upto plinth level -1:2:4 (1 cement :2 coarse sand : 4 graded stone aggregate 20mm nominal size).	0.60 Cum		1 Cum	
5.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	1.90 Cum		1 Cum	

.....2/-

6.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.10 Cum		1 Cum	
7.	Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns	19.00 Sqm		1 Sqm	
8.	Providing , hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but excluding cost of reinforcement , with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	0.60 Cum		1 Cum	
9.	Steel reinforcement for R.C.C. work including straightening, cutting , bending , placing in position and binding all complete upto plinth level – Thermo - Mechanically treated bars (TISCO / VIZAG / IISCO / SAIL / JSW) Fe - 415 or more.	58.00 Kg.		1 Kg.	
10.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc .complete - 40mm thick with 20mm nominal size stone aggregate.	2.00 Sqm		1 Sqm	
11.	6mm cement plaster of mix 1:3 (1 cement : 3 fine sand).	11.00 Sqm		1 Sqm	
12.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - nominal concrete 1:3:6 or richer mix (including equivalent design mix).	0.50 Cum		1 Cum	
13.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead nominal concrete 1:4:8 or leaner mix (including equivalent design mix).	0.75 Cum		1 Cum	
14.	Providing and fixing on wall / column face unplasticed - PVC soil and waste pipes (type - B) conforming to IS : 13592- 1992 including jointing with seal ring conformation to IS : 5382 leaving 10mm gap for thermal expansion - single socked pipes -110mm diameter.	56.00 Metres		1 Metre	

.....3/-

2. Quotation will be received by the undersigned up to 3.30 pm on 28-04-2022 and opened at 4.00 p.m. on the same day.
3. EMD amount at 2% of the quoted amount should be remitted along with quotation in the form of Demand Draft in favour of the Commissioner, Oulgaret Municipality. The Quotation should be valid for 90 days from the date of opening.
4. The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof.
5. The firm /contractor should be able to start the above work immediately on receipt of the work order and complete the same within 30 days from the date of receipt of work order.
6. The rate quoted should be inclusive of all charges viz. GST, Transportation etc..
7. Payment will be made on satisfactory completion of the work in all respects within the stipulated period.


**COMMISSIONER
OULGARET MUNICIPALITY**

Copy to:

1. Notice Board, Oulgaret Municipality.