



F.No.32-21/AE-IV/JE(6)/OM/2022-23

**OULGARET MUNICIPALITY
PUDUCHERRY - 5**

Jawahar Nagar, the 03.11.2022

QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractor by the undersigned for the following work:

Name of Work: Reconstruction of damaged 'U' drain along the 8th cross street at Brindavanam.

Sl. No.	Description	Quantity	Rate per unit	Total amount
1.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	2.50 Cum		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.50 Cum		
3.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. upto floor five level, excluding the cost of centring ,shuttering and finishing - 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	9.50 Cum		
4.	Centering and shuttering including strutting , propping etc. and removal of form work for - retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	45.00 Sqm		
5.	Providing , hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centring, shuttering but excluding cost of reinforcement , with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal	0.50 Cum		

6.	Steel reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding all complete upto plinth level - Thermo - Mechanically treated bars (ISI BRAND OF APPROVED MAKE) Fe - 415 or more	36.00 Kgs.		
7.	6mm cement plaster of mix - 1:3 (1cement : 3 fine sand)	35.50 Sqm		
8.	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - in cement mortar	10.50 Cum		
9.	Desilting the canal by removing silt, slush and debris from the bed of the drain removing the grass , bushes etc., complete in unhygienic and foul condition including disposal of the same within an average lead of 1KM without polluting the environment by manual means	4.50 Cum		

Quotation will be received by the undersigned up to 3.30 pm on 11.11.2022 and opened at 4.00 p.m. on the same day.

EMD amount at 2.00% of the quoted rate should be remitted in the form of demand draft in favour of the Commissioner, Oulgaret Municipality. Quotation should be valid for 90 days from the date of opening.

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof. The Oulgaret Municipality Council is competent to accept any quotations.

The firm / contractors should complete the work within 15 days from the date of receipt of work order.

The rate quoted should be inclusive of all charges viz. tax, transporting etc.


(A.SURESHRAJ)
COMMISSIONER

Copy to:

1. Notice Board, Oulgaret Municipality.
2. Oulgaret Municipality Website.