



F.No.32-42/AE-IV/JE(6)/OM/2022-23

**OULGARET MUNICIPALITY
PUDUCHERRY - 5**

Jawahar Nagar, the 13.04.2023

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors by the undersigned for the following work:

Name of Work: Reconstruction of damaged 'U' drain / Causeway at Thendral Nagar and Rajivgandhi Street at Samipillaithottam in Kamaraj Nagar Constituency.

Sl. No.	Description	Quantity	Rate per unit	Total amount
1.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size).	1.50 Cum		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:3:6 (1 cement : 3coarse sand : 6 graded stone aggregate 20mm nominal size).	10.00 Cum		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size).	2.50 Cum		
4.	Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns.	7.00 Sqm		
5.	Centring and shuttering including strutting , propping etc. and removal of form work for - retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	54.00 Sqm		
6.	Steel work welded in built up sections /framed work , including cutting,hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required - in stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required all complete.	703.50 Kgs.		

7.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc .complete - 40mm thick with 20mm nominal size stone aggregate	75.00 Sqm		
8.	6mm cement plaster of mix - 1:3 (1 cement : 3 fine sand)	89.00 Sqm		
9.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	4.00 Cum		
10.	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - in cement mortar.	10.50 Cum		
11.	Desilting the canal by removing silt, slush and debris from the bed of the drain removing the grass, bushes etc., complete in unhygienic and foul condition including disposal of the same within an average lead of 1KM without polluting the environment by manual means.	11.50 Cum		

Quotation will be received by the undersigned up to 3.30 pm on 19.04.2023 and opened at 4.00 p.m. on the same day.

EMD amount at 2.00% of the quoted rate should be remitted in the form of demand draft in favour of the Commissioner, Oulgaret Municipality. Quotation should be valid for 90 days from the date of opening.

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof. The Oulgaret Municipality Council is competent to accept any quotations.

The firm / contractors should complete the work within 15 days from the date of receipt of work order.

The rate quoted should be inclusive of all charges viz. tax, transporting etc.


(A.SURESHRAJ)
COMMISSIONER

Copy to:

1. Notice Board, Oulgaret Municipality.
2. Oulgaret Municipality Website.

Quotation notice