



F. No. 31-53/ AE-II/JE(3)/OM/2023-24
OULGARET MUNICIPALITY
PUDUCHERRY - 5

Jawahar Nagar, the 11-9-23

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors for the work of **"Improvements to the road branching from ECR Leading to Saibaba Temple in Kalapet, Puducherry"** by the undersigned as mentioned below:

Sl. No.	Description of Item	Quantity	Rate (Rs.)	Unit	Amount (Rs.)
1.	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m - all kinds of soil.	41.50 cum		cum	
2.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	5.00 cum		cum	
3.	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth three wheeled steel roller 8-10 tonnes in stages to proper grade and camber, applying and brooming Requisite Crushable type such as moorum / gravel for screening and gravel for binding to fill up the interstices of coarse aggregate, watering and compacting to the required density - by manual means -Water bound macadam Gr-I with Gravel screening. (As per MoRTH specification, 4th Revision).	23.50 cum		cum	
4.	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth 3 wheeld steel roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite Crushable type such as moorum or gravel for screening and gravel for binding to fill up the interstices of coarse aggregate, watering and compacting to the required density - by manual means - Water bound macadam Gr-II with moorum or gravel screening. (As per MoRTH specification, 4th Revision).	18.00 cum		cum	

5.	Cleaning the existing W.B.M. road surface including removing of binding material and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment. As per clause no 502.4.2 and 503.3.1 of MOST specification. and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil.	335.00 sqm		sqm	
6.	Cleaning of the existing black topped surfaces with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment. As per clause no 503.3.1 of MOST specification.	1175.00 sqm		sqm	
7.	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means. (As per MoRTH specification, 4th Revision).	335.00 sqm		sqm	
8.	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg. per sqm. on the prepared bituminous / granular surface cleaned with mechanical broom. (As per MoRTH specification, 4th Revision).	1175.00 sqm		sqm	
9.	Providing and laying bituminous macadam with hot mix plant of capacity not less than 40 -60 TPH using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 507.7 of MoRTH specification, 4th Revision, to achieve the desired compaction. - using grade II metal and bitumen 60/70 grade.	5.00 cum		cum	
10.	Providing and laying semi-dense bituminous concrete with HMP of capacity not less than 40 - 60 TPH using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per clause 508 of MoRTH specification, 4th Revision, complete in all respects - Using grade-I material and bitumen 60/70 grade.	35.50 cum		cum	

11.	Providing and laying of hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads@250gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	12.00 sqm		sqm	
-----	---	--------------	--	-----	--

CONDITIONS:

Quotation will be received by the undersigned up to 3.30 pm on 21-9-2023 and opened at 4.00 p.m. on the same day.

EMD amount at 2% of the quoted amount should be remitted in the form of Demand Draft in favour of the Commissioner, Oulgaret Municipality. The Quotation should be valid for 90 days from the date of opening.

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof.

The firm /contractor should be able to start the above work immediately on receipt of the work order and complete the same within 2 months from the date of receipt of work order.

The rate quoted should inclusive of all charges viz. GST, Transporting etc.

Payment will be made on satisfactory completion of the work in all respects within the stipulated period.


COMMISSIONER
OULGARET MUNICIPALITY

Copy to:

1. Notice Board, Oulgaret Municipality.