



F.No.32-09/AE-IV/JE(6)/OM/2023-24

**OULGARET MUNICIPALITY
PUDUCHERRY – 5**

Jawahar Nagar, the 22/9/2023

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firm's/contractor's by the undersigned for the following work:

**Name of Work: Desilting and providing safety grill to the canal at Brindavanam
in Kamaraj Nagar Constituency.**

Sl. No.	Description	Quantity	Rate per unit	Total amount
1.	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil.	4.50 Cum		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size).	5.00 Cum		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.00 Cum		
4.	Providing ,hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands , copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	1.00 Cum		
5.	Steel reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding all complete upto plinth level - Thermo - Mechanically Treated bars (ISI BRAND OF APPROVED MAKE) Fe - 415 or more.	143.00 Kgs.		

6.	Steel work welded in built up sections / framed work , including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required - in stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required all complete.	993.00 Kgs.		
7.	Desilting the canal by removing silt, slush and debris from the bed of the drain removing the grass , bushes etc., complete in unhygienic and foul condition including disposal of the same within an average lead of 1KM without polluting the environment by manual means.	73.50 Cum		
8.	Removing and refixing the precast RCC drain cover slab of varying thickness on top of U drain including laying in position to the required level and alignments etc., complete as directed by the Engineer-in-charge.	8.00 Sqm		
9.	Extra for disposal of excavated sludge for additional lead of 2km including loading and unloading etc., as directed by the Engineer-in-Charge.	73.50 Cum		

Quotation will be received by the undersigned up to 3.30 pm on ~~29.9.2023~~ and opened at 4.00 p.m. on the same day.

EMD amount at 2.00% of the quoted rate should be remitted in the form of demand draft in favour of the Commissioner, Oulgaret Municipality. Quotation should be valid for 90 days from the date of opening.

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof. The Oulgaret Municipality Council is competent to accept any quotations.

The firm / contractors should complete the work within 30 days from the date of receipt of work order.

The rate quoted should be inclusive of all charges viz. tax, transporting etc.


(A.SURESHRAJ)
COMMISSIONER

Copy to:

1. Notice Board, Oulgaret Municipality.
2. Oulgaret Municipality Website.

Quotation notice