



F.No.32-29/AE-IV/JE(6)/OM/2024-25
OULGARET MUNICIPALITY
PUDUCHERRY - 5

Jawahar Nagar, the 14-11-2024

QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors by the undersigned for the following work:

Name of Work: Providing rainwater harvesting arrangements to the Park at Rainbow Nagar in Kamaraj Nagar Constituency.

Sl. No.	Description	Quantity	Rate per unit	Total amount
1.	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as per direction of Engineer-in-charge, within a lead of 50m - all kinds of soil	6.00 Cum		
2.	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and all lift.	2.00 Cum		
3.	Supplying and filling in plinth with river sand under floors, including watering, ramming consolidating and dressing complete.	0.50 Cum		
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:2:4 (1 cement : 2 fine aggregate : 4 graded stone aggregate 20mm nominal size).	1.50 Cum		
5.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 fine aggregate : 10 graded stone aggregate 40mm nominal size)	0.75 Cum		
6.	Centring and shuttering including strutting, propping etc. and removal of form work for - foundations, footings, bases for columns	6.00 Sqm		
7.	Providing, hoisting and fixing above plinth level upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but excluding cost of reinforcement, with 1:1.5:3 (1 cement : 1.5 fine aggregate : 3 graded stone aggregate 20mm nominal size)	0.50 Cum		

...2/-

8.	Steel reinforcement for R.C.C.work including straightening , cutting , bending , placing in position and binding all complete below plinth level - Mild steel and Medium Tensile steel bars	72.00 Kgs.		
9.	Cement plaster 1:3 (1 cement : 3 fine aggregate) finished with a floating coat of neat cement - 20mm cement plaster	4.00 Sqm.		
10.	Providing and fixing cement concrete rings of 900 mm dia. 300mm height and 40 mm thick in 1:2:4 (one cement , two sand , and four 12mm HBG metal) with slots in the walls and provided with nominal reinforcement . The rate to include the cost of cement concrete rings, transportation to site , labour for erection , fixing with cement mortar 1:3 (one cement and three sand) all complete	6.00 Nos.		
11.	Supplying and lowering of UPVC 150mm dia Plain casing pipe conforming to IS: 12818-1992 with relevant amendments with class designation CM and with minimum wall thickness of 7.5 mm as per I.S.Code into the bore well with proper vertical alignments etc. Including the cost of materials , but excluding the cost of labour for positioning the assembly for lowering purpose using contractor's rig	12.00 Rmt.		
12.	Extra for providing 3mm slots in 150 mm dia .UPVC casing pipes	10.00 Rmt.		
13.	Supplying and packing of 8mm size down gauge graded pebble including filling the annual space gradually complete. The pebbles should be of free from disintegrated pieces.(It will measure in stack for the purpose of payment).	2.00 Cum		
14.	Providing and fixing netlon mesh	1.00 Sqm		
15.	Providing, laying and jointing UPVC pipes (0.6 Mpa) conforming to IS specification 4985 and ISI marked including transportation to the site , lowering to the trenches, laying to proper grade and alignment, testing of joints with required testing equipment, including cost of solvent cement, excluding UPVC specials such as bends, tees, threaded pieces, couplers ,reducer, end caps etc., complete all as per IS and CPWD specification. - 200mm dia.	25.00 Meters		

16.	Drilling of borewell any where in UT of Pondicherry including transportation in alluvial soil, sedimentary strata of clay, sand stone, shale, pebbles, boulders etc. by first taking a pilot bore of 140mm / 150mm / 200mm and then enlarging to required dia by direct or reverse rotary mud circulation method, including fuel, labour for drilling, bentonite mud, water required for drilling at the site, construction of mud pit (water available within a lead of 1.5Km) using rotary rig. -Upto 60 mts depth ending below ground level.	25.00 Meters		
17.	Reaming from 200 mm dia pilot bore to 350mm dia bore. Upto 60 mts depth ending below ground level	25.00 Meters		
18.	Charges for developing the borewells with air compressor of 600 CFM capacity including transportation labour and fuel charges for compressor and conducting yield test by "V" Notch methods.	8.00 Hours		
19.	Lowering of UPVC plain casing pipe/ribbed screen slotted pipes into the borewell including cost of cleaning material, fixing of M.S centring guide size of 25mm x 3mm thick suitable for 200mm dia UPVC pipe, including cost of labour for positioning of assembly for lowering purpose using rig.	2.00 Nos.		
20.	Providing and fixing M.S. top cover suitable for UPVC pipes including the cost of materials and labour etc.	1.00 No.		
21.	Providing and fixing of UPVC End Cap embedded in M.S. Cone suitable for UPVC casing pipe including the cost of materials and labour for jointing.	1.00 No.		
22.	Providing and fixing RCC NP2 collar of 1200mm dia, 300mm height and 40mm thick in 1:2:4 (one cement, two sand and four 12mm HBG metal) with slots in the walls and provided with nominal reinforcement. The rate to include the cost of cement concrete rings, transportation to site, labour for erection, fixing with cement mortar 1:3 (one cement and three sand) all complete.	5.00 Nos.		


Quotation will be received by the undersigned up to 3.30 pm on 21.11.2024 and opened at 4.00 p.m. on the same day.

EMD at 2.00% of the quoted amount should be remitted in the form of demand draft in favour of the Commissioner, Oulgaret Municipality. Quotation should be valid for 90 days from the date of opening.

...4/-

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof. The Oulgaret Municipality Council is competent to accept any quotations.

The rate quoted should be inclusive of all charges viz. tax, transporting etc.


(A.SURESHRAJ)
COMMISSIONER

Copy to:

1. Notice Board, Oulgaret Municipality.
2. Oulgaret Municipality Website.