



F.No.32-40/AE-IV/JE(6)/OM/2024-25
OULGARET MUNICIPALITY
PUDUCHERRY - 5

Jawahar Nagar, the 06.12.2024

SHORT QUOTATION NOTICE

On behalf of the Municipal Council sealed quotations are invited from the eligible firms/contractors by the undersigned for the following work:

Name of Work: Reconstruction of damaged culvert and providing cover slab over the existing 'U' drain at Venkata Nagar Park in Kamaraj Nagar Constituency..

Sl. No.	Description	Quantity	Rate per unit	Total amount
1.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:1.5:3 (1 cement : 1.5 fine aggregate : 3 graded stone aggregate 20mm nominal size)	4.50 Cum		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:3:6 (1 cement : 3 fine aggregate : 6 graded stone aggregate 20mm nominal size)	2.50 Cum		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 fine aggregate : 10 graded stone aggregate 40mm nominal size)	4.25 Cum		
4.	Centring shuttering including strutting's, propping etc. and removal of form work for : Retaining walls , return walls, walls (any thickness) including attached pilasters, buttresses plinth and string courses fillets etc.- Using steel sheet with M.S.frames.	15.00 Sqm		
5.	Providing , hoisting and fixing above plinth level upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centring, shuttering but excluding cost of reinforcement , with 1:1.5:3 (1 cement : 1.5 fine aggregate : 3 graded stone aggregate 20mm nominal size)	4.00 Cum		
6.	Steel reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding all complete upto plinth level - Thermo -Mechanically treated bars Fe - 500D or more.	702.00 Kgs.		

7.	Steel work welded in built up sections / framed work , including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required - in stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required all complete	810.00 Kgs.		
8.	Cement concrete flooring 1:2:4 (1 cement :2 fine aggregate : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick with 20mm nominal size stone aggregate.	6.00 Sqm		
9.	6mm cement plaster of mix 1:3 (1 cement : 3 fine aggregate).	11.00 Sqm.		
10.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. - Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	2.50 Cum		
11.	Demolishing R.C.C work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	1.50 Cum		

Quotation will be received by the undersigned up to 3.30 pm on -13-12-2024 and opened at 4.00 p.m. on the same day.

EMD at 2.00% of the quoted amount should be remitted in the form of demand draft in favour of the Commissioner, Oulgaret Municipality. Quotation should be valid for 90 days from the date of opening.

The Oulgaret Municipal Council reserves right to reject any or all the quotations without assigning any reason thereof. The Oulgaret Municipality Council is competent to accept any quotations.

The rate quoted should be inclusive of all charges viz. tax, transporting etc.


(A.SURESHRAJ)
COMMISSIONER

Copy to:

1. Notice Board, Oulgaret Municipality.
2. Oulgaret Municipality Website.